# Technical Bulletins

# Constructing & Commissioning Freezers Treated With An allnex Floor Topping



Constructing & Commissioning Freezers treated with an allnex floor topping must be well managed and planned. Incorrect applications, applications at incorrect temperatures will lead to delamination and premature failure.

Rapid thermal shocking can damage the concrete substrate and /or the allnex floor topping, therefore the commissioning process of a freezer is very critical to avoid undue stresses and prevent possible structural damage to the concrete floor slab and/or the allnex floor topping.

We are unaware of any industry standard for the commissioning process so we have listed below the critical aspects and procedures that have proved successful over many years.

## **Basic Requirements for the Concrete Floor Slab**

- Must be minimum 25mpa compressive strength.
- Must be cured minimum 28 days.
- Moisture content less than 75% RH, 18% WME or 4% actual moisture content.

#### Note:

Trapped moisture will expand within the concrete when frozen, the concrete must be able to withstand the tensile forces created.

#### allnex floor topping

- Installation must be carried out at ambient temperature +10°C (resin floor topping will not cure at temperatures below 5°C)
- Once installed it is very important that the topping is allowed to fully cure at the ambient positive temperature and become stable before reducing the temperatures or putting the freezer back into service. Full cure generally takes 5 - 7 days at >20°C/75% RH.
- o Once fully cured,
- o The designed topping will be able to operate in a freezer range -50°c − +25°c.
- However it is important to avoid rapid constant temperature cycling, decreasing and increasing of the freezer temperature should be controlled and carried out over a 24 hour period.


#### Cove details

It is considered best practice to isolate the floor from the freezer walls to avoid cracking due to differential movement or compression of the insulation under the floor when fully loaded.

Cracking from walls or the concrete substrate that reflect through the topping are not floor topping failures.

## Cove Isolation Options;

- a. Using a flexible adhesive;
  - adhere a cove support plate to the surface of the freezer panel walls, apply the cove over the support plate, thereby isolating the cove from the wall to allow for differential movement.
  - Install a cold joint at the foot of the cove for complete separation.
- b. No Cove Details, See freezer detail drawings below.



# **Freezer Commissioning Process**

The condensers in the freezer units are very effective at removing moisture from concrete and may be utilised to speed the dry of the concrete floor slab.

Once the new topping has been installed and allowed to cure the freezer can be commissioned;

Step 1 Lower temperature to 0°C and hold for 2 days.

Step 2 Lower temperature at 5°C increments and hold for 2 days at the temperature.

Step 3 Repeat the process until required temperature is achieved.

For further advice or information do not hesitate to contact the allnex technical team.

Free Ph: 0508 88 22 88

E-mail: <u>cs.constructionnz@allnex.com</u>
Website: <u>www.allnexconstruction.com</u>

Date: Aug 2019 Replaces Sept 2015

Allnex Construction Products, a Division of Allnex New Zealand Ltd

Auckland - 14 Industry Road Penrose phone: 095836544. Hamilton - 18 Somerset Street Frankton phone: 07-847-8658

Wellington - 19A Jamaica Drive Grenada North phone: 04-240-0305. Christchurch - 112 Carlyle Street Sydenham phone: 03-366-6802

Customer Service: 0508-882-288 cs.constructionnz@allnex.com

www.allnexconstruction.com

allnex

DISCLAIMER: This information appearing in this Document (Details) concerning the product which is the subject of the Document (Product) is either based on present technical knowledge and tests done by allnex or tests done by, and data supplied from third parties including you, the customer. Since the actual use by you and by others of the Product is beyond the control of allnex, no warranty or representation, express or implied is made by allnex regarding the suitability for such use, nor does allnex accept any liability arising out of the use by you of other products or materials, whether third party or not, that may be referred to in this Document, allnex recommends that you carry out you row tests as to the suitability of the Product for your purpose, regarding which you accept full responsibility. In addition, if any of the Details appearing in the Document are based upon tests done by, and/or data supplied by any third party, allnex provides no warranties or representations in connection with those Details and you, the customer waives any right you may have against allnex in connection with the accuracy, completeness or otherwise of the Details. The information in this Document is not to be construed as absolutely complete or accurate since additional information may be necessary or desirable when particular or exceptional conditions or circumstances exist or because of applicable laws or government regulations affecting use of the Product allnex does not provide any warranty or representation to you that the Product does not infringe the intellectual property rights of any third party. All orders accepted shall be subject to the standard conditions of sale of allnex which are on the back of our invoice. In accepting the Product you, the customer and agree: a) The Product is or inhered to a care and the product of the product and the product and product any supervising government. b). The Product is a care and that you, the customer, are responsible for the disposal of the container housing the Product in